
ECO-TRE

Textured, chamfered edges give these pavers an authentic stone feel yet provide a 10% open surface area. Joint opening that is compliant with the Americans with Disabilities Act. (ADA)




Environmental Pavers







ECO-TRE



DISCLAIMER: These typical details are provided for general information purposes only. Anyone making use of these details does so at their own risk and assumes all liability for such use. Site specific design should be performed by a licensed professional engineer who is familiar with actual site conditions, soil, other materials and local practices.

NOTES:

- 1. Subgrade must have adequate bearing capacity and be suitable for infiltration practices. Do not compact unless specified by design engineer.
- 2. Pavers, aggregate base and subbase must be properly compacted.
- 3. # 2 stone may be replaced with # 3 or # 4 stone.
- 4. Pavers shall be installed with a surface tolerance of ±3%" over 10ft with no paver lippage greater than 1/2"
- 5.. Consult ICPI's current permeable pavement design manual for design and installation information.



